



NOTES:

1. TRENCH SIDE SLOPES SHALL BE IN ACCORDANCE WITH OSHA REQUIREMENTS. BEGIN SIDE SLOPES, IF USED, APPROXIMATELY 18" ABOVE TOP OF PIPE (TYPICAL ALL BACKFILL TYPES).
2. CONTRACTOR MUST PROVIDE SOME MEANS OF BRACING TO PREVENT FLOTATION OF THE SEWER LINE PRIOR TO THE POURING OF CONCRETE.

CONCRETE ENCASEMENT

DETAIL

NO SCALE

